

Reconstruction Fürther Gate in Nürnberg

Contractor: City of Nürnberg
Hochbauamt

Period fixed: 1999 - 2000

Building costs: ca. 0,5 Mio. €

Fee zone: III

Output PSS:

Remedial design development, Project-and
Support structure planning phases 2-5
Tender and Site management.

Project data:



The Fürther gate was 1894 broke into the old city walls and valuated with a tunnel. The breakthrough was a city wall tower to the victim.

The tunnel has a width of 11.00 m and a height of 2.30 m at the abutments and 4.60 m at the apex.

Simultaneously with this project, the planning proceeded for a restoration on the building called Köchertzwinger. Of the buildings is given nothing more. (War destruction, or rather removal or walls still standing after the war). After the passage was built over pre-war through the restaurant above the masonry arch no sealing. Since the war here humus and proliferation accumulated.

Partial remains of the old ground could be seen covering. This in turn led to a complete in 1998/99 visible by humidification of the vault and considerable damage to this, which by chipping stone in winter.

